



**BID TABULATION FOR ROADWAY AND PARKING LOT REPAIRS
PROJECT NO. 11-018A
Bid Opening: October 4, 2011 at 2:00 p.m.**

Company Name	Bid Bond or Check	Base Bid ^A	Alternate Bid Item 1 ^B	Additional Calendar Days	Deductive Bid Item 1 ^C	Deduct Calendar Days	Time of Delivery*	Addendum No. 1
Garrett Construction Company	5% Bid Bond	\$366,741.00	\$155,532.60	10	(\$127,343.65)	5	90	X
Haas-Anderson Construction Ltd.	5% Bid Bond	\$443,000.00	\$180,488.50	0	(\$120,470.60)	0	100	X
Berry Contracting Lp dba Bay Ltd	5% Bid Bond	\$523,172.30	\$197,731.68	30	(\$143,464.80)	30	75	X

*In calendar days

^A BASE BID: Work includes A.1: reconstruction 2,810 ft. - Rincon Rd from Burleson Ave to Fulton Corridor; scarifying top 4" existing base material, re-grade, compact, and add 4" of new limestone base, prime coat and Type C HMAC PG 70-22 surface. A.2: Reconstruction 1,620 ft of McBride Ln from Up River Rd to OD-6 entrance, scarifying top 4" existing base material, re-grade, compact, and add a prime coat and a 2" Type C HMAC PG 70-22 surface. A.3: New construction extending Avery Dock Rd 265 ft to the west of Oil Dock 11, excavation, compaction of existing sub grade, adding 6" of Type A Grade 1 limestone base, prime coat and 2" Type "C" HMAC PG 70-22 surface. A.4: Includes, 1,800 sf concrete pavement repairs to Bulk Dock Rd.- 300 sf full depth repairs and

^B ALTERNATE BID ITEM 1: Reconstruction 2,810 feet of Rincon Road from Burleson Ave. to the Fulton Corridor. The work will entail excavation of the top 4-inches of the existing base material, re-grade and compact sub grade. Install Tensar BX 1100 geogrid, return 4" of excavated base material and add 4" of new limestone base, a prime coat and a 2" Type "C" HMAC (PG 70-22) surface. This is a Lump Sum bid item.

^C DEDUCTIVE BID ITEM 1: Deduct the reconstruction of Rincon Rd included or described in the Base Bid A.1. This is a Lump Sum.

Read By: Greg Brubeck, P.E.

Tabulated By: Bert Perez, P.E.

Checked & Prepared By: Melinda Maldonado

Date: October 4, 2011